	Particulars	Quantity	Per unit	Rate
4.	(a) Roofing with 24 B. W. G. corrugated G. I. sheets with galvanised screws, bolts washers, sheets to overlap 1″ at ends and two corrugations at sides complete.	46·20	Sqrs.	
	(b) Ridge sheeting 24 B. W. G., G. I. sheeting 2′ wide to overlap 9″ at ends fixed complete with G. I. bolts, nuts and lead washers.	83	R.ft.	
	(c) T. W. panelled doors 2″ shutters with fixtures etc., complete.	180	S.ft.	
	(d) T. W. windows with glazed shutters 1¼″ thick and expanded metal netting on the out side (1½″x¾″x 3/8) complete.	504	,,	
	(e) Teak wood glazed circular ventilators 1¼″ shutters, etc.	14	,,	
	(f) Fixing iron clamps to doors and windows 12″x2″x¼″	40	No.	
9.	Constructing " U " shaped drain 9″x9″ with brick jelly in surki mortar concrete and ½″ thick cement plastering.	300	R.ft.	

C. SITARAMIAH,
Superintendent,
Mysore Power and Lighting

MYSORE RAILWAYS.

MYSORE DIVISION (OPEN LINES).

Notification dated 20th August 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Open Line Division, Mysore Railways, Mysore, up to 2 P.M., on the 25th September 1928, from contractors who are willing to undertake the construction of new Indian Refreshment Room at Maddur.

2. Every tender should be accompanied by an earnest money of Rs. 100, which can be paid either in currency notes to the Executive Engineer, Mysore Railways, Mysore along with the tender; or can be paid to the Auditor, Mysore Railways, Mysore, and the receipt thereof enclosed along with the tender. Such of the tenderers who pay the amount to the Auditor should advice him that the amount is paid on account of a tender for the construction of new Indian Refreshment Room at Maddur.

(a) Tenders should be submitted in special forms which can be obtained from the Executive Engineer, Mysore Railways, Mysore, on payment of Re. 1.

3. The earnest money of the unsuccessful tenderers will be returned as soon as possible after the tenders are disposed of.

4. Tenders which are not accompanied with the earnest money specified in para 2, will not be considered.

5. The successful tenderer should execute within a week from the date of notification of acceptance of his tender, the usual Railway Schedule Agreement Failure to comply with this condition will render the tenderer liable for forfeiture of the earnest money

6. The name of the accepted tenderer will be posted on the Notice Board of the Executive Engineer's Office. No. enquiries regarding the acceptance or rejection of a tender will be replied.

7. The final acceptance of the tender will rest with the Agent, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender and who further reserves to himself the right to reject, without assigning any reason therefor, any or all the tenders.

8. Work should be started within a week from the date of acceptance of tender, and a uniform monthly rate of progress should guaranteed. The work agreed on should be completed in eight months from date of starting. The accompanying Schedule gives the approximate quantity of work and this quantity is not guaranteed.

9. The time limit specified in para 8 should be strictly adhered to and any violation of this will render the contractor liable to forfeit his 5 per cent deposit amount under Clause No. 10 of the Schedule Agreement, not as a penalty but as ascertained and liquidated damages recoverable accordingly

10. Plans and specifications and other details of work to be done are available for inspection in the Executive Engineer's Office, Mysore Railways, Mysore, where intending tenderers may call and obtain required information during office hours.

11. In all matters of dispute regarding rates, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Engineer-in-Chief will be final and legally binding.

SCHEDULE.

Serial No.	Description of work	Unit	Quantities for		Remarks
			Main building	Out house	
1	Farthwork excavation	100 C.ft.	3,555	1,928	
2	Concrete in sand mortar	100 ,,	1,183	601	
3	Burnt brick in mortar (foundation and basement).	100 ,,	1,993	1,197	
4	Burnt brick in mud superstucture ...	100 ,,	2,816	2,427	
5	Arch work burnt brick in mortar ..	C.ft.	32	...	
6	Burnt brick in mortar	100 C.ft.	828	399	
7	Burnt stone slabs 6" thick neatly dressed ...	S.ft.	585	185	
8	Plastering with mortar	Sqr.	79·67	54·03	
9	White and colour washing	,,	79·67	54·03	
10	Flooring with Cuddapah slabs over 3" concrete bed including cement pointing.	,,	6·77	...	Slabs to be obtained under Ry, materials concession rates.
11	Flooring with Marsailles tiles on 3" concrete bed including cement pointing.	,,	3·60	...	
12	Flooring with 3" concrete and cement plastering, 1/2" thick	,,	7·20	6·19	
13	Cut stone pillars 6" to 8" square two-line dressed 7 feet high and chamferred with base and capitel as per approved design.	No	15	...	
14	Teakwood wrought and put up, including woodoiling.	C.ft.	120·14	39·41	
15	Roofing with First Class Mangalore tiles with teak reepers 2" x 1" including chunam borders, etc., complete.	Sqr.	31·29	14·55	Tiles to be obtained uuder Railway materials concession rates.
16	Ridge tiles set in mortar	R.ft.	137	73	
17	Valleys with G. I. sheeting with 1/2" thick plank including cement, mortar, etc.	S.ft.	66	....	
18	Teakwood doors with shutters, 1/3rd glazed and 2/3rd panelled with hinges, hasps, etc., complete as per approved design.	,,	416	...	
19	Fly-proof shutters to the doors as per approved design.	,,	416	...	
20	Teakwood windows with double shutters inside half glazed and half fly-proof separately and outside panelled shutters including iron bars, fittings, etc., complete, as per approved design.	,,	210	..	
21	Teakwood ventilators glazed with iron bars	,,	36	32	
22	Teakwood circular ventilators, glazed	,,	7	...	
23	Teakwood eave board 9" x 1", ornamental including painting as per approved design.	R.ft.	371	...	
24	Teakwood finials, large, including painting as per approved design.	No	3	...	
25	Teakwood finials, small including painting, as per approved design.	,,	12	...	
26	Painting with silver grey paint ...	Sqr.	12·95	...	
27	Teakwood sunshade, large, as per approved design including painting.	No.	1	...	
28	Teakwood sunshade, small as per approved design including painting.	,,	4	...	
29	Teakwood doors battened with shutters, hinges, hasp and staple locks. etc., complete as per design.	S.ft	...	235	
30	Teakwood windows with iron bars, doors, hinges, etc., complete as per approved design.	,,	...	36	
31	Coping with burnt brik in clay and plastered with mortar.	R.ft.	...	36	
32	Painting with chocolate	Sqr.	...	4·60	

Serial No.	Description of work	Unit	Quantities for		Remarks
			Main building	Out house	
33	Constructing oven	Each	...	4	
34	Constructing cistern with sink as per approved dimensions.	,,	...	2	
35	Providing pestle and mortar approved size...	,,	...	2	
36	Fly-proof shutters to doors and windows as per approved design.	S.ft.	...	62	
37	Wall racks on T. W. pegs and T. W. planks 1½" thick, as approved.	,,	...	212	

Abstract Notification dated 17th August 1928.

Attention of the public is hereby invited to the Notice calling for tenders for the Construction of Quarteas for Station Staff at Badanagappe and Narasambudi Stations on Nanjangud Chamarajnagar Railway, published in pages 810 and 811 of Part VI of *Mysore Gazette*, dated 16 August 1928.

M. RAMAIYA,
Executive Engineer.

HASSAN DIVISION (OPEN LINES).

Abstract.

Sealed tenders are invited for the work of building stone revetment to the slopes of the approach banks of Lakshmanathirtha bridge on the Mysore Arsikere Section up to 2 P.M., on 31st August 1928, by the undersigned. For details, please see the Notification dated 10th August 1928, published in the page 837 Part VI, of the *Mysore Gazette*, issued on 23rd August 1928.

V. RAMANUJALU NAIDU,
Executive Engineer.

NOTICE.

Applications will be received for the entertainment of 12 Apprentices in the Railway Workshops at Mysore—6 of Class "A" and 6 of Class "B".

The Educational qualifications required and the scale of daily wages allowed are noted below.—

Class	Educational qualification	Scale of wages in annas		
"A"	... Must have passed sixth standard.	1st year	...	... 8
		2nd ,,	...	... 12
		3rd ,,	...	... 16
		4th ,,	...	.. 20
		5th ,,	...	... 24
"B"	... Must have passed fourth standard.	1st year	...	... 6
		2nd ,,	...	... 9
		3rd ,,	...	... 12
		4th ,,	..	... 15

The minimum age for "A" Apprentice will be 16 years and for "B" 14 years.

Applications should reach the undersigned before the end of August 1928.

H. S. AERS,
Loco and Carr Superintendent,
Mysore Railways, Mysore.